



# ALBUQUERQUE VAULT COMPANY

PRE-CAST  
CONCRETE  
PRODUCTS

300 Airport Dr., NW \* Albuquerque, NM 87121 \* Phone: 505-836-4404 / Fax: 505-836-5663

Detail #

ST-3000

Not To Scale

Dec., 2012

## 3,000 GALLON SEPTIC SYSTEM INSTILLATION UTILIZING 2 BOXES

### GENERAL NOTES:

1. Design specifications conform to latest ASTM C1227 specifications for "Precast Concrete Water and Wastewater Structures,"
2. Pipe penetration locations per job requirements. Pipe inlet and outlet locations to have cast-in-place boots. Pipe to be installed by contractor.
3. Inlet and outlet requirements such as tee's and/or effluent filter supplied and installed by contractor.
4. A minimum of 3" fall required from outlet to inlet between the 2 tanks.
5. Casting / Top provided and installed by contractor / customer per job requirements. 2", 3", 4" & 6" grade rings can be supplied by Albuquerque Vault Co. or field adjusted, using approved methods by contractor.
6. Excavation hole bottom shall be 2' wider & 2' longer than total outside dimensions.
7. O.D. = outside dimension  
I.D. = inside dimension

